



KEY NOTES

- $\langle 03 \rangle$ Slope ceiling 2 in. per foot
- 05) Concrete slab
- $\langle 06 \rangle$ Tile
- $\langle 08 \rangle$ Wood or steel stud framing
- $\langle 10 \rangle$ Blocking
- 21) Pre-pitch mortar bed, slope 1/4 in. per foot to drain
- (22) Mortar bed
- (24) Cementitious bond coat
- (29) Cement backer board
- (31) Reinforcement as req'd
- (35) Drain assembly
- 41 Rigid insulation
- 59 Weep protector
- 61) Vapor retarder, optional
- 62) Shower pan membrane, fold up walls min. 3 in. above top of curb (curb not shown)
- 63 Continuous bonded waterproof membrane
- (74) Sealed slip joint (perimeter expansion joint)
- (78) Shim as req'd
- (95) Ceiling framing

KEYWORDS

Steam room, Steam shower, Watertight installations, 06.110.0614, SR614, backer board, metal stud framing, wood stud framing, mud floor

TITLE

SCALE

SHEET NO

Tile Steam Room Assembly | Wood or metal studs, backer board walls, mud floor

none

04/06/20 | 0

06.110.0614